BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B

Package No-11

1.Providing Children playing equipments and gym equipments at Allalasandra Lake in ward No.04 of Yelahanka Division

2.Providing Children playing equipments and gym equipments in ward No.02,03 and 04 Yelahanka Division

3.Providing Grill Fencing to Selected parks in Ward No.02, 03 & 04 of Yelahanka Division

4.Providing Grill Fencing and Construction of Badminton court at Allalasandra Lake in Ward No.04 of Yelahanka Division

5.Providing Grill Fencing at Someshwara Hill lake in Ward No.03 of Yelahanka Division

SNo	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
1	2253.28	Removing and resetting of kerb stones. complete as per specifications and directions of the Engineer in charge.	m	105.88	Rupees One Hundred Five And Paise Eighty
2	3934.00	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete., complete as per specifications and directions of the Engineer in charge.	m	436.98	Rupees Four Hundred Thirty Six And Paise Ninety Eight Only
3	432.00	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint complete as per specifications and directions of the Engineer in charge.	m	436.98	Rupees Four Hundred Thirty Six And Paise Ninety Eight Only
4	157.27	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. complete as per specifications and directions of the Engineer in charge.	Cum	5563.25	Rupees Five Thousand Five Hundred Sixty Three And Paise Twenty Five Only
5	1925.30	Providing and applying painting in two coat with Synthetic enamel paint of approved brand and manufacture on concrete surface with cost of materials ,labour ,complete as per specifications.complete as per specifications and directions of the Engineer in charge.	Sqm	85.66	Rupees Eighty Five And Paise Sixty Six Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
6	1902.74	Providing and laying heavy duty cobble stones 60mm thick interlock pavers,using cement and course sand for manufacturer of blocks of approved size,shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed(average Thinkness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to comeup in between joints , final compaction of pavers surfaces joint into its final level including cost of materials,labour and HOM complete as per specifications. complete as per specifications and directions of the Engineer in charge.	Sqm	1128.05	Rupees One Thousand One Hundred Twenty Eight And Paise Five Only
7	2.85	KSRRB M200-12.2. Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. i) Lime /Cement Concrete. I. By Manual Means :B. Cement Concrete Grade M-15 & M-20. MORTH Specification. (5km lead = 57+2*1.28X5). complete as per specifications and directions of the Engineer in charge.	Cum	667.01	Rupees Six Hundred Sixty Seven And Paise One Only
8	1015.70	Dismantling of barbed wire fencing / wire mesh fencing including posts, foundation concrete, back filling of pit by manual means including disposal of dismantled material with all lifts and stacking serviceable material and unserviceable material separately complete as per specifications. MORTH Specification. complete as per specifications and directions of the Engineer in charge.	m	71.23	Rupees Seventy One And Paise Twenty Two Only
9	432.61	Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. complete as per specifications and directions of the Engineer in charge.	cum	4923.19	Rupees Four Thousand Nine Hundred Twenty Three And Paise Nineteen Only
10	299.94	Providing and constructing granite / trap / basalt size stone masonry in superstructure with cement mortar 1:4 , edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, scaffolding, curing complete as per specifications.complete as per specifications and directions of the Engineer in charge.	Cum	6432.39	Rupees Six Thousand Four Hundred Thirty Two And Paise Thirty Nine Only
11	589.02	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications..complete as per specifications and directions of the Engineer in charge.	Sqm	152.08	Rupees One Hundred Fifty Two And Paise Seven Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
12	126.16	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.43cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.complete as per specifications and directions of the Engineer in charge.	Cum	5707.63	Rupees Five Thousand Seven Hundred Seven And Paise Sixty Two Only
13	646.04	Supplying and fixing M.S rectangular poles made out of two equal angles of 65X65X6 mm welded together and fixed in CC 1:2:4 with two numbers 16mm dia M.S hold fast rods each of length 25cms including cost of all materials cutting, bending scaffolding whereever necessary, nicely finishing the welded jonts with all lead lift and as per the direction of engineer incharge of the work and including providing two coats of approved quality paint over coat of shop painting (excluding cost of earthwork and concrete)..complete as per specifications and directions of the Engineer in charge.	m	920.15	Rupees Nine Hundred Twenty And Paise Fifteen Only
14	2418.00	Fabricating providing and erecting in position of MS Hot Dip galvanized sq hallow poles of 132 x132 heavy gauge length 3000mm with MS Hot Dip galvanized grill work as per approved design and drawing of chief architect using 12 x75mm galvanized flat for alround frame and 20 x 20mm galvanized forged ornamental arrow head in top and buttom the work is inclusive of throughing flat square rods placing welding all the joints including griding finishing 2 coats of anticorrossive paint over one coat of metal primer the rate is inclusive of all materials all items of work cost painting welding cutting griding with lead and lift as per specifications including loading and unloading with cost and conveyance of all materials labour machinery and incidental charges for the successful completion of the work as per direction of engineer in charge of work.	Sqm	9240.96	Rupees Nine Thousand Two Hundred Forty And Paise Ninety Six Only
15	1131.31	Providing chain link fencing 50mm size of 8 guage properly stretched between rectangularpoleas and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour lead and lift and as per the directions of the engineer incharge of work including two coats of approved quality paint over one coat of shop paint. completion of the work as per direction of engineer in charge of work.	Sqm	765.19	Rupees Seven Hundred Sixty Five And Paise Nineteen Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
16	27.90	Providing and fixing M.S Gate as per Chief Architect Drawing , using 50mm x 50mm x 14 gauge M.S hollow pipe frame work bent to ornamental shape as shown in the drawing and 35mm x 6mm and 16mm x 16mm Square rods for verticals alternatively spaced at 4cms c/c in two halves and 40 mm x 6mm M.S flats for horizontal member and at the top cast iron spikes are provided at alternate vertical members as shown in the drawing etc., complete. all the steel surface should be throughly cleaned free of rust and painted with anti materials , labour charges for all items of work , Hire charges for welding , cutting and grinding eqipment , electricity charges , with lead and lift , loading and unloading charges , etc.completion of the work as per direction of engineer in charge of work.	Sqm	3226.30	Rupees Three Thousand Two Hundred Twenty Six And Paise Thirty Only
17	56.40	Fabricating, providing and erecting in position Hot dip galvanized Gate. Using 72x72x4.8 mm Sq. G I Pipe Frame with top pipe bending in heavy duty hydraulic press with sand packing and hot bending to form double arch as per drawing profile, 20mm hot dip galvanized sq.rod for verticals at 150mm c/c , as shown in the drawing including providing hot do galvanized forged ornamental design in between rods and heads at top, middle and bottom. Intermediate supports of 75x12mm and 50x6mm arch bent to hot dip galvanized flats.The work is inclusive of throughing GI, Flat GI Sqm. rods, placing, welding all the joints including grinding, finishing metal patty, painting two coats enamel painting. The rate is inclusive of all materials Like GI Sq. GI Pipe, GI Forged designs etc., heavy duty hinges are made out of 75mm sold sq. block assembled with 20mm du bearing in three places for each flop. Heavy duty locking arrangement of low places including cost of labour, painting, erection charges using hoist pulley cranes, with all lead and lift, loading, trasportation, unloading, scaffolding charges and all other.completion of the work as per	Sqm	12606.83	Rupees Twelve Thousand Six Hundred Six And Paise Eighty Two Only
18	839.71	Providing and applying enamel metal paint two coats (exclusive primer coat) over new steel or other metal surfaces brushing to give an shade after cleaning oil grease dirt and other forien matters including cost of materials labour complate as per specifications. completion of the work as per direction of engineer in charge of work.	Sqm	101.06	Rupees One Hundred One And Paise Six Only
19	143.23	PROVIDING TRAPEZOIDAL PROFILED SHEET Providing and installing of pre painted Galvolume iron Trapezoidal profiled sheet of approved make 1060 mm width (1000 mm cover width), 28-30 mm crest height with crest distance of 200 mm c/c with 2 ribs at the centre for stiffening. The total coated thickness (TCT) of the sheet will be 0.47 mm +/- 0.02 mm tolerance Zinc-Alu Alloy coating AZ150 gsm as per ASTM 1397/A755-550 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 20-22 microns using self drilling/self tapping screws of 25 mm length, to be fixed over the existing purlins, rafters, channels and trusses.completion of the work as per direction of engineer in charge of work.	Sqm	736.31	Rupees Seven Hundred Thirty Six And Paise Thirty One Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
20	589.99	Earthwork excavation By manual means for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. (5km lead = 57+2*1.28X5). completion of the work as per direction of engineer in charge of work.	Cum	390.78	Rupees Three Hundred Ninety And Paise Seventy Eight Only
21	285.00	Providing and filling sand in trenches to required depth including watring ramming with all leads and lift complete as per specifications and directed by the engineer incharge at the site.completion of the work as per direction of engineer in charge of work.	cum	2206.05	Rupees Two Thousand Two Hundred Six And Paise Five Only
22	182.60	Providing and constructing load bearing wall with solid concrete blocks of size 400x200x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 5.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications..completion of the work as per direction of engineer in charge of work.	Sqm	976.94	Rupees Nine Hundred Seventy Six And Paise Ninety Four Only
23	111.54	Providing and laying/fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick for flooring conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, mortar including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification. completion of the work as per direction of engineer in charge of work.	Sqm	1319.59	Rupees One Thousand Three Hundred Nineteen And Paise Fifty Nine Only
24	2.00	Supply & fixing of children multi play equipment with spiral slide, monkey bar with number pannel . Upright structural posts of height 4.2 m are to be hot dip galvanized steel with a 114 mm OD and 2.2mm wall thickness of tubing . Roof of size 1.9m x 1.7m x 0.77 m , spiral slide of size2.56m x 1.85m x 2.68m. Top rails of monkey bar size 1.8m x 1.3m are all robotic welded & fabricated from 48mm OD galvanized steel pipes for the outer bars &32 mm OD galvanized steel for the inner parallel bars with a baked on powder coated finish. Deck of size 1.45 x 1.45 m are pressed and punched , welded ,sand blasted ,powder coated to 2.2mm thickness or vinyl coated to a thickness of 4mm . Deck of size 1.45 x 1.45 m are pressed and punched , welded ,sand blasted ,powder coated to 2.2mmthickness or vinyl coated to a thickness of 4mm. Deck, step, platform ,stairs, baffle shall be all robotic welded. Inclined ramps of size 1.92m x 0.65m , stair case of size 1.5m x 0.77m are fabricated from solid 2mm perforated solid punched steel Frisbee climber , piped walls of size 1 m are robotic welded , fabricated from 32 mm OD galvanized steelpipes for outer and 25mm OD galvanized steel	Each	1936256.44	Rupees Nineteen Lakh(s) Thirty Six Thousand Two Hundred Fifty Six And Paise Forty Four Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
25	1.00	Supply and fixing of childern Multi Play Equipment with double swing, curved side toddler slide with animated roof Upright structural posts of height 2.7 m and 3 m are to be schedule HOT DIP Galvanized steel with a 114mm OD and 2.2mm (wall) thickness of the tubing. The poles are welded on to a base plate made from steel with 114mm inner diameter. Deck of size 1.45 x 1.45m and Staircase of size 1.48 m x 0.60 m are fabricated from 2mm perforated solid punched steel. Deck perimeter is precision pre punched for attachments. Handrail of height 1.90 m and Dia 32 mm shall be an all-robotic welded unit, fabricated from 32 O.D. galvanized steel pipes with a baked on powder coating finish. Exposed hardware shall be covered with ultra violet stabilized plastic safety caps as per Sun Roof of size 2.0 m x 1.78 m x 0.77m, Spiral Slide of size 2220 mm x 1630 mm x 1880 mm , Straight Slide of size 1645 mm x 800 mm x 1140 mm, Panels. Roofs and panels are copyrighted and IP protected worldwide. Spring Climber of thickness Dia 38 mm, 3 step ladder , Frisbee Climber ,Piped walls of Height 2.7 m are all robotic welded fabricated from 32	Each	1229647.65	Rupees Twelve Lakh(s) Twenty Nine Thousand Six Hundred Forty Seven And Paise Sixty Five Only
26	1.00	Supply and fixing of childern Multi Play Equipment with curved slide and number panel : Upright structural posts of height 2.4 m, 2.7 m, 3.3 m schedule HOT DIP Galvanized steel with a 114mm OD and 2.2mm (wall) thickness of the tubing. All metal components are to be finished with a baked on powder coat finish.With deck of size 1.45 x 1.45m and Staircase of size 1.5m x 0.77 m are fabricated from 2mm perforated solid punched steel. Deck perimeter is precision pre punched for attachments. Decks are pressed, punched, and welded sand blasted and vinyl plastic coated to a thickness of 4mm. Along with Handrail of height 2.2 m and Dia 32 mm shall be an all-robotic welded unit, fabricated from 32 O.D. galvanized steel pipes with a baked on powder coating finish.Curved Slide of size 1.94 m x 1.85 m x 2.4 m, Panels,Toprails Of Monkey loop of size 1.8 m x 1.3 m.Deck of size 1.45 x 1.45m are fabricated from 2mm perforated solid punched steel. Deck perimeter is precision pre punched for attachments. Decks are pressed, punched, and welded sand blasted and vinyl plastic coated to a thickness of 4mm. Roof of size Dia 2 m and height 0.82 m,	Each	2224684.00	Rupees Twenty Two Lakh(s) Twenty Four Thousand Six Hundred Eighty Four Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
27	4.00	Supply and fixing of childern Multi Play Equipment :Upright structural posts of height 2.35 m , 3.0 m and 3.25 m are to be schedule HOT DIP Galvanized steel with a 114mm OD and 2.2mm (wall) thickness of the tubing. Handrail of height 2.20 m and Dia 32 mm shall be an all-robotic welded unit, fabricated from 32 O.D. galvanized steel pipes with a baked on powder coating finish. Snake Ladder Climber of size 0.99 m x 0.62 m x 1.20 m with thickness of Dia 38 mm, Piped walls of Height 2.6 m are all robotic welded fabricated from 32 O.D. galvanized steel pipes for the outer pipes and 25mm O.D. galvanized steel for the inner parallel bars with a baked on powder coat finish. crab Roof of size 1.9 m x 1.7 m x 0.77m, Sun Roof of size 2.0 m x 1.78 m x 0.77m, Straight slide 2.28 m x 0.83 m x 1.20 m , Spiral Slide of size 2.22 m x 1.60 m x 1.5 m, Rock climber of size 1.03 m x 0.70 m x 1.20 m Panel. The rates are to be inclusive of supply and installation at site. Inclusive of All Taxes and Transportation Charges..completion of the work as per direction of engineer in charge of work.	Each	1514825.81	Rupees Fifteen Lakh(s) Fourteen Thousand Eight Hundred Twenty Five And Paise Eighty One Only
28	5.00	Supply and fixing of childern Play Equipment Two seater seesaw : The See Saw consists of 2 poles of Dia 114mm and thickness of 2.5mm which balances the horizontal rod at the center which is of size 3110 mm length and Dia 114 mm. It consists of 2 seats which is made of LLDPE virgin plastic of size 305mm X 213 mm X 125 mm. The rates are to be inclusive of supply and installation at site. Inclusive of All Taxes and Transportation Charges.completion of the work as per direction of engineer in charge of work.	Each	84365.05	Rupees Eighty Four Thousand Three Hundred Sixty Five And Paise Five Only
29	1.00	Supply & fixing of Arm & Pedal Bike : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the	Each	214757.81	Rupees Two Lakh(s) Fourteen Thousand Seven Hundred Fifty Seven And Paise Eighty One Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
30	1.00	Supply & fixing of Big Shoulder Wheel : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the	Each	151593.75	Rupees One Lakh(s) Fifty One Thousand Five Hundred Ninety Three And Paise Seventy Five Only
31	1.00	Supply & fixing of Elliptical Cross Trainer: All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the	Each	176859.38	Rupees One Lakh(s) Seventy Six Thousand Eight Hundred Fifty Nine And Paise Thirty Eight Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
32	1.00	Supply & fixing of Pull Down Challenger : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the	Each	299145.00	Rupees Two Lakh(s) Ninety Nine Thousand One Hundred Forty Five Only
33	1.00	Supply & fixing of Seated Chest Press : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the	Each	290554.69	Rupees Two Lakh(s) Ninety Thousand Five Hundred Fifty Four And Paise Sixty Nine Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
34	1.00	Supply & fixing of Rider : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the	Each	113695.31	Rupees One Lakh(s) Thirteen Thousand Six Hundred Ninety Five And Paise Thirty One Only
35	1.00	Supply & fixing of Tai Chi Spinners : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the	Each	145276.86	Rupees One Lakh(s) Forty Five Thousand Two Hundred Seventy Six And Paise Eighty Six Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
36	1.00	Supply & fixing of HD Sit Up Station : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the	Each	157909.68	Rupees One Lakh(s) Fifty Seven Thousand Nine Hundred Nine And Paise Sixty Seven Only
37	1.00	Supply & fixing of HD Squat Pushing : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the	Each	271604.99	Rupees Two Lakh(s) Seventy One Thousand Six Hundred Four And Paise Ninety Nine Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
38	1.00	Supply & fixing of HD Health Walker :All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out in excess of at least 50 public park projects in India either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCL solution in	Each	176859.38	Rupees One Lakh(s) Seventy Six Thousand Eight Hundred Fifty Nine And Paise Thirty Eight Only
39	1.00	Supply & fixing of HD Mini Ski :All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out in excess of at least 50 public park projects in India either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCL solution in	Each	201215.44	Rupees Two Lakh(s) One Thousand Two Hundred Fifteen And Paise Forty Four Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of Sri. KOLA VENKATA KRISHNA REDDY (RAMKRISHY INFRASTRUCTURE PRIVATE LIMITED)	
				In figures	In words
40	1.00	Supply & fixing of HD Waist Twister :All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out in excess of at least 50 public park projects in India either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCL solution in	Each	164226.56	Rupees One Lakh(s) Sixty Four Thousand Two Hundred Twenty Six And Paise Fifty Six Only
41	113.17	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clodscomplete as per specifications and directions of the Engineer in charge.	Cum	327.25	Rupees Three Hundred Twenty Seven And Paise Twenty Five Only
42	624.00	Bored / Cast-in-situ R.C.C. . piles with OPC cement design mix M20 @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.46cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008 excluding reinforcement as per drawings including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH Specification complete as per specifications and directions of the Engineer in charge.	m	12344.06	Rupees Twelve Thousand Three Hundred Forty Four And Paise Six Only
43	6.02	Providing and laying in position plain cement concrete of mix 1:4:8(M7.5)with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregtes @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.complete as per specifications and directions of the Engineer in charge.	Cum	5568.06	Rupees Five Thousand Five Hundred Sixty Eight And Paise Six Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone